

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>K-1, L-1</u>
2. PROPERTY CONTROLLING IN SECTION <u>1</u>	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

ALGER
CO.

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Rabbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on November 15 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-1** Northwest section corner; wood post; sugar 13" - N40°E - 26 lks.; sugar 15" - N74°W - 38 lks.; beech 8" - S20°E - 20 lks.; fir 12" - S50°W - 47 lks.
- L-1** North 1/4 corner; wood post; sugar 12" - N38°E - 3 lks.; sugar 12" - N51°W - 24 lks.
- 1** West 1/16 corner on north section line; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-1** Corner set at narrow gauge RR iron not of record. Conforms well with corners east and west.
- L-1** Corner set at narrow gauge RR iron not of record. Conforms well to corners east and west, and old blaze line north.
- 1** Set M.P.O.L. between the N. 1/4 corner and the N.W. section corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL** 1" pipe, 4" aluminum cap
- K-1** 5" h. maple - S43°W - 9.8'; 9" h. maple - N38°W - 12.2'; 10" h. maple - N59°E - 38.8'; 8" h. maple - S28°E - 47.8'
- L-1** 5" h. maple - S22°E - 15.8'; 10" h. maple - S53°W - 17.2'; 4" h. maple - N74°W - 10.5'; 14" h. maple - N53°E - 10.5'
- 1** 6" h. maple - N65°W - 26.7'; 10" h. maple - N70°W - 31.5'; 16" h. maple - S65°W - 31.0'; 4" h. maple - S33°W - 33.2'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558