

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>G-4, G-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

ALGER CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 15 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-4 Wood post - Cedar 12-N60°E - 29 links; Black ash 10-S45°W - 29 links.
- G-5 Wood post - cedar 12-N25°W - 2 links; Spruce 18-S42°E - 37 links.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-4 Set from N.E. O.B.T. STP. tree was cut about 5' above ground - STP. had fallen over both upper and lower face plain some scribing on lower face but mostly rotted away.
- G-5 Found 2 old sq. (2"x2") cedar stakes 16" cedar windfall for N.W. O.B.T. old face for upper blaze a "T" legible in the over growth on upper blaze.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-4 1" pipe with 4" aluminum cap; 6" cedar - S54°W - 8.1'; 15" cedar - N11°E - 28.2'.
- G-5 1" pipe with 4" aluminum cap; 18" cedar - N31°W - 67.8'; 9" spruce - N9°W - 96.9'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ DATE _____