

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. S., R. 22 E.	J-5, K-5, K-7
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

ALGER CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 24 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- J-5 Wood post - Yellow birch 12-N45°W - 18 links; black ash 15-S33°E - 8 links.
- K-5 Wood post - Cedar 12-N30°W - 18 links; cedar 10-S20°E - 41 links.
- K-7 Wood post - Cedar 12-N50°W - 11 links; spruce 12-S18°E - 17 links.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-5 Set mid point on line, no evidence of any other survey found.
- K-5 Found old stake bottom - cedar stump in place for S.E. O.B.T. too rotted for any marks. Several blazed trees facing corner.
- K-7 Found 2' of 1 1/2" pipe and old post point - cedar stub 5' tall -N50°W - 11 links. For N.W. O.B.T. the face is badly burned but some scribing still plain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-5 1" pipe with 4" aluminum cap; 5" cedar - N81°E - 20.7'; 8" cedar - north - 29.6'
- K-5 1" pipe with 4" aluminum cap; 6" cedar - S8°W - 7.0'; 5" cedar - S83°W - 8.7' (old blaze 1 1/2" spruce - N45°E - 1.8' (old blaze); 8" cedar - S41°E - 21.6'.
- K-7 1" pipe with 4" aluminum cap; 6" cedar - S60°W - 9.6'; 6" cedar - S39°E - 12.5'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)