

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>G-1, M-1</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

ALGER
CO.

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan F.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 15 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-1 Wood post - Cedar 10-N38°E - 12 links; Cedar 8-N29°W - 25 links.

M-1 Wood post - Tam. 14-S60°E - 26 links; Tam. 16-N70°W - 8 links.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-1 Found R.R. rail - no O.B.T.'s position fits well with occupied lines and other corner monuments in the area.

M-1 Found R.R. Rail - 4"x4" square cedar post rotted off and lying on the ground-blazed scribed cedar N.B.T. N.W. (not of record) - stumps in place for O.B.T.'s tam: 16 - N70°W - 8, Tam. 14" - S60°E - 26, both very rotten.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Section of R.R. Rail; 10" cedar - N11°W - 7.7'; 10" cedar - southwest - 24.5';

M-1 Section of R.R. Rail; 9" cedar - N12°E - 13.1'; 8" cedar - S70°E - 27.5'; 12" cedar N64°W - 16.4' (old N.B.T.).

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____