

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 22 W


Alger COUNTY

DESCRIPTION OF CORNER Section Corner Common to Sections 4, 5, 8 and 9

CORNER MONUMENT One-inch galvanized pipe with four-inch brass cap

DATE MONUMENT PLACED AND WITNESSED May 16, 1961

WITNESSES TO CORNER..... Red Maple 7" N 73 W 34 links



Yellow Birch 18" N 1 E 22.5 links

Sugar Maple 9" N 67 E 44.5 links

AND

Elm 7" S 36 E 12.5 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was located by A. Metsa and A. Eger on 10/4/57. Both the tamarack and birch trees were down. The tamarack was badly decayed but a hard slab showed the face but no scribe marks. The birch face had grown over but by chopping out the overgrowth we uncovered the face which showed the scribe marks very distinctly. A 1-1/2 iron pipe was in place but not secure; also an old wooden post. Monument was set and new bearing trees scribed by A. Metsa.

SURVEYOR'S SEAL

SIGNED

Aime A. Metsa
REGISTERED LAND SURVEYOR

DATE

5/17/61