

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 22 W


Alger COUNTY

DESCRIPTION OF CORNER Section Corner Common to Sections 5, 6, 7 and 8

CORNER MONUMENT One-inch galvanized pipe with four-inch brass cap

DATE MONUMENT PLACED AND WITNESSED May 18, 1961

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

Black Spruce 8" N 36 W 108 Links

Black Spruce 6" N 84 W 35 Links

AND

Black Cherry 9" N 20 E 26.5 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set from an original birch bearing tree. The tree was down and decayed but both faces, which had grown over but had been chopped out at a much later date, were plain. The lower face showed part of the scribe marks very distinctly. The other bearing tree (hemlock) had completely rotted away. A dead hemlock stub nearby had been faced and written on at least 50 years ago.

Corner was found by A. Metea and A. Eager on 2/27/59.

SURVEYOR'S SEAL

SIGNED

Arne A. Metea
REGISTERED LAND SURVEYOR

DATE

5/19/61