

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 NR 22 W

Alger

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 17, 18, 19, 20

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER 11" Cedar N 51° E 69 links  
#S 17 NBT

7" Cedar S 75° W 11 links  
#S 19 NBT

8" Cedar N 46° W 53 links  
#S 18 NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from Cedar and B. Ash B.T.s. Found old Cedar stake in proper position.

Cedar B.T. bearing N 27° W 10 links has been cut above description base. Scribe marks plain. Stump in good condition.

B. Ash B.T. bearing S 9° E, 12 links. Tree still green but rotted on inside.

Evidence of use by several signatures on Cedar B.T.

Allen Smith  
H. F. Smith 8/29/29  
Slater 6/1/51  
J. O. Pryle  
P. H. Miller 7/10/56

Section corner found by Arne Metsa, D.F., with the help of Angus Macafee, Kiva. Corner placed and witnessed 1/25/57.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*

REGISTERED LAND SURVEYOR

DATE 2-7-57