

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 .. NR. 22 W ..

Alger

COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 10, 15

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER 1 1/2" Y. Birch S 61° W 50 links
"1/4 S NBT"

10" Hard Maple S 16° E 47 links
(Birdseye) "1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner from one Hemlock B.T. in place.
Tree still green; description blaze and scribe marks in excellent condition. B.T. bears N 52° W, 24 links.
No evidence of Maple B.T.

Evidence of use by several blurred names written on B.T.
Old blaze line running to West.

N & S logging road 8 1/2 chains West of Corner.

1/4 Corner found by B. Borak, Ass't District Forester 2/27/56.

Corner place and witnessed 1/25/57.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2-7-57
REGISTERED LAND SURVEYOR