

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 45 N R. 22 W


ALGER COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Sections 17 and 18

CORNER MONUMENT One-inch galvanized pipe with 1/2-inch aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 18, 1962 by A. Metea

WITNESSES TO CORNER..... Elm 8 N 50 E 52 links



Sugar Maple 10 S 60 E 57.5 links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set from the two original BT's. Both trees live but in poor shape. The birch now 28" in diameter and leaning. The upper face has been chopped out long ago but now badly decayed and scribe marks not visible. Butt of tree shows scar where lower face was grown over, but because of decayed condition of inside of tree did not attempt to chop out the face. The maple now 20" in diameter, upper face chopped out first about 70 years ago and again about 40 years ago. Center has rotted completely out, leaving the tree hollow, and scribe marks erased. Scar at butt shows where lower face grew over, but because of decayed and hollow condition of tree did not chop out lower face. Trees fit field notes in species, size, bearing and distance. Old post set near birch BT but off of proper location by 5 feet. Old blazes run N & S from this point and more recent blazes run west. Stream occurs 6 1/2 ch. south of cor. instead of 4 1/2 as called for in field notes but conditions are such that stream could have been 4 1/2 ch. south at time of original survey.

SURVEYOR'S SEAL

SIGNED

A. Metea  
REGISTERED LAND SURVEYOR

DATE

10/31/62