

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 NR. 22W

-----Alger----- COUNTY

DESCRIPTION OF CORNER ----- Sec. cor. common to secs: 10-11-14-15 -----

DESCRIPTION OF CORNER MONUMENT ----- 1" Pipe with 4" Brass Cap -----

WITNESSES TO CORNER ----- 13" Y. Birch (S11 NBT) N25°E 57 Lks. -----

----- 13" H. Maple (S14 NBT) S15°E 53 Lks. -----

----- 12" H. Maple (S15 NBT) S56°W 64 Lks. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced cor. from one Elm B.T. bearing N53°W 33 Lks. This tree has been cut and butted in recent logging operations. Scribe marks evident on both blazes. Cor. placed and wit. 2/24/59 with Art Enger, Ass't D.F.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 8/11/59  
REGISTERED LAND SURVEYOR