

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>23-22</u> E. W.	<u>A-5, A-6, A-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on May 16 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- A-5 N.W. corner - Sec. 18; Wood Post, Sugar 8 - S53°E - 29 lks.; Birch 12 - N22°W - 26 lks.; Y. Birch 18 - N30°E - 16 lks.
- A-6 West 1/4 corner - Section 18; Wood Post, Cedar 12 - S88°W - 25 lks.; Cedar 12 - N62°E - 16 lks.
- A-7 S.W. corner - Section 18; Wood Post, Birch 10 - N76°E - 45 lks.; Hemlock 12 - S60°W - 7 lks.; Cedar 16 - S50°E - 52 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- A-5 Found 3/4" pipe and old N.B.T., 18" R. Maple - S10°E - 7.90' (probably county witness).
- A-6 Found 3/4" pipe and two old N.B.T.s not of record but fits other corner locations in the area well.
- A-7 Set by projecting a line from the West 1/4 corner of Sec. 18 across the line tree recorded in G.L.O. notes as "21.18 - W. Pine 60 in. diam." (found tree cut but not removed - Hack Marks plain). Proportioned distance South from line tree to match our measurement from the W. 1/4 corner to the line tree as compared to the G.L.O record. Fits swamp and stream calls west and north.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- ~~ALL - 1" pipe, 4" aluminum cap.~~
- A-5 - 9" R. Maple - N5°E - 22.60'; 5" H. Maple - S73°E - 11.25'; 6" W. Spruce - S10°W - 36.30'; 9" R. Maple - N61°W - 26.65'.
- A-6 - 9" Cedar - S85°E - 12.35' (old witness); 8" Cedar - S53°W - 11.65' (old witness); 5" Cedar - S54°E - 24.60'; 13" Cedar - S87°W - 18.70'.
- A-7 - 4" Balsam Fir - N48°W - 15.60'; 5" R. Maple - N22°E - 14.40'; 4" R. Maple - S39°E - 23.50'; 4" Balsam Fir - S4°W - 7.80'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt DATE 12-18-79  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558