

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>F-3, G-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 26 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- F-3 N 1/4 corner - Section 9; Wood Post, Sugar 15 - N40°W - 21 lks.; Sugar 12 - S62°E - 23 lks.
- G-3 N.E. Corner - Section 9; Wood Post, Hemlock 10 - N72°W - 20 lks.; Hemlock 14 - S65°E - 21 lks.
- 2 E. 1/16 corner on the north section line - Section 9; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-3 Set M.P.O.L. between the N.E. and N.W. section corners of Section 9.
- G-3 Set by double prop. measurement to G.L.O. record using section corners 1 mile west - 1 mile north and 2 miles east and 1/4 corner 1/2 mile south. This monument falls in front of a 28" living hemlock with plain scribing showing "R22W-T45N-3" which appears to be an unrecorded witness from the original government survey.
- 2 Corner falls one chain east from swamp edge. Set M.P.O.L. between the N 1/4 corner and the N.E. section corner of Section 9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL - 1" pipe, 4" aluminum cap.
- F-3 - 8" Hard Maple - N52°W - 10.2'; 4" Hard Maple - N6°E - 9.6'; 7" Hard Maple - S35°E - 30.1'; 8" Hard Maple - S53°W - 27.2'.
- G-3 - 22" Hemlock - N11°W - 50.7'; 28" Hemlock - N45°E - 18.7' - probable unrecorded witness from the original government survey; 10" Hard Maple - S75°E - 35.2'; 8" Red Maple - S16°W - 30.2'.
- 2 - 7" Cedar - S47°E - 21.1'; 6" Cedar - S26°W - 38.0'; 6" Cedar - S85°W - 35.4'; 8" Hemlock - N43°E - 29.5'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 12-18-79
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558