

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>3, 7, 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 20 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- 3 N. 1/16 corner on the West line of Section 11; not previously established.
- 7 N 1/16 corner on the East section line - Section 11; not previously established.
- 14 S 1/16 corner on the East section line - Section 11; not previously established.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- 3 Set M.P.O.L. between the West 1/4 corner and the N.W. section corner of Sec. 11. Falls tight against the North side of an 18" elm in wet area.
- 7 Set M.P.O.L. between the N.E. section corner and the East 1/4 corner of Section 11.
- 14 Monument set against south side of a 14" elm tree - true corner position (M.P.O.L.) falls in the tree.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- ALL - 1" pipe, 4" aluminum cap.
- 3 - 13" Cedar - N85°E - 25.6'; 10" Hemlock - N33°E - 27.1'; 12" Bl. Ash - N30°W - 34.9'; 11" Y: Birch - S59°W - 31.2'.
  - 7 - 8" Cedar - S58°E - 29.6'; 4" Cedar - N84°E - 27.4'; 4" Cedar - N44°E - 33.9'; 8" Cedar - N59°W - 6.1'.
  - 14 - 3" H. Maple - S42°W - 11.2'; 8" H. Maple - S15°E - 17.9'; 6" H. Maple - N84°E - 32.1'; 9" H. Maple - N3°W - 12.6'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt DATE 12-18-79  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558