

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>I-3</u>
2. PROPERTY CONTROLLING IN SECTION	<u>3</u> T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>1, 3</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 20 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-3 S.E. section corner - Section 3; Wood Post, Sugar 12 - N48°W - 24 lks.; Y. Birch 10 - S58°E - 33 lks.
- 1 West 1/16 corner on North section line; not previously established.
- 3 North 1/16 corner on the West section line - Section 3; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-3 Set by double prop. measurement to G.L.O. record. Using section corners 1 mile east - 1 mile north - 1 mile south and 2 miles west.
- 1 Set mid-point on line between the N.W. section corner and the N 1/4 corner of Section 3.
- 3 Set by prop. measurement to G.L.O. record. On line between the N.W. Section corner and the West 1/4 corner of Section 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL - 1" pipe, 4" aluminum cap.
- I-3 6" Sugar Maple - S32°E - 24.7'; 6" Y. Birch - S71°W - 21.3'; 4" Sugar Maple - N51°W - 22.0'; 5" R. Maple - N73°E - 35.9'.
- 1 10" Cedar - S18°W - 15.9'; 4" Yellow Birch - N83°W - 13.2'; 3" Cedar - N46°E - 11.7'; 6" Hemlock - S60°E - 14.7'.
- 3 11" Cedar - N84°W - 16.8'; 4" Cedar - N9°W - 22.6'; 5" Cedar - S2°E - 8.4'; 6" Cedar - N89°E - 23.0'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 12-18-79
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558