

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>B-5, C-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>18</u>	, T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 27 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-5 North 1/4 corner - Sec. 18; 18" long section of railroad rail set by James O'Rouark no N.B.T.s noted.
- C-5 N.E. Section corner. Used in survey by James O'Rouark in 1903 but no description of corner was given.
- 2 East 1/16 corner on the North section line - Section 18; James O'Rouark - 1903 set maple post and section of railroad rail about 18" long.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-5 Found section of railroad rail 18" long as described in notes of a survey by James O'Rouark dated July 2, 1903 in which he states "found B.T.s to correspond exactly maple on Section 18 preserved." - No sign of O.B.T.s at this time.
- C-5 Set by projecting a line from the N 1/4 corner across the East 1/16 corner on the North section line and doubling the distance as shown in the notes of a survey by James O'Rouark, dated 1903 several old blazed trees around this monument.
- 2 Found section of railroad rail set monument beside it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-5 - 6" H. Maple - N27°W - 8.10'; 4" H. Maple - N75°E - 16.15'; 10" Y. Birch - S58°E - 24.70'; 9" Y. Birch - S71°W - 29.70'; 1" pipe, 4" aluminum cap.
- C-5 - 1" pipe, 4" aluminum cap; 6" Hard Maple - S23°W - 19.4'; 6" Hard Maple - S28°E - 26.7'; 10" Hemlock - N22°E - 39.9'; 10" Hard Maple - N46°W - 33.9'.
- 2 - 1" pipe, 4" aluminum cap; 13" Bl. Cherry - S63°W - 41.45'; 9" Maple - N86°W - 34.2'; 10" Ironwood - N5°E - 20.0'; 6" Ironwood - N76°E - 33.6'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt DATE 12-18-79
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558