

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>D-5, E-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>17</u>	, T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 25 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- D-5 North  $\frac{1}{4}$  corner - Section 17; Wood Post, Spruce 16 - N45°E - 55 lks.; Fir 15 - S50°W - 12 lks.
- E-5 N.E. corner - Section 17; Wood Post, Sugar 10 - N25°W - 8 lks.; Lynn 10 - S35°E - 20 lks.
- 2 East 1/16 corner on the north section line of Section 17; not previously established.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- D-5 Set M.P.O.L. between the N.E. and N.W. section corners of Section 17.
- E-5 Found square cedar stake. Not of record but fits the location of surrounding corners well. No sign of O.B.T.'s. Replaced stake with D.M.R. monument.
- 2 Set M.P.O.L. between the North  $\frac{1}{4}$  corner and the N.E. section corner of Section 17.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- ALL 1" pipe, 4" aluminum cap.
- D-5 19" Cedar - S74°E - 73.5'; 4" Maple - N84°E - 26.95'; 7" Maple - N48°W - 23.05'; 19" Cedar - S24°W - 9.9'.
- E-5 6" Cedar - N40°W - 14.3'; 5" Sugar Maple - N63°E - 6.4'; 6" Sugar Maple - S59°E - 9.7'; 15" Cedar - S42°W - 18.6'; Corner lies on East edge of swamp.
- 2 15" Y. Birch - S57°W - 35.3'; 8" Sugar Maple - N58°W - 16.9'; 5" Cedar - N78°E - 14.8'; 8" Sugar Maple - S50°E - 38.8'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR DATE 1-26-81 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558