

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46. NR. 17. W.

Alger COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 1, 2, 11, 12

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER 9" Cedar N 49° W 17½ links
"S 2 NBT"

8" Cedar N 67° E 44 links
"S 1 NBT"

6" Cedar S 37° E 14 links
"S 12 NBT"

9" Cedar S 34° W 60 links
"S 11 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from one Tamarack B.T.
Tree bears S 11° E, 32 links, bottom of stump with notch and scribe marks "BT" remaining.

Evidence of use by several old names and numerous blazes in area.
Corner lies in Cedar Swamp.
Section Corner found by Forestry Division Survey Crew while making a partial re-survey of this township.

Corner placed and witnessed 1-28-57.

SURVEYORS SEAL

SIGNED Billy O. Buchler DATE 2-7-57
REGISTERED LAND SURVEYOR