

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T47-46 NR 17 W..

Alger

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 35, 36, 1, 2

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER 12" Cedar S 47° W 56 1/2 links

10" White Pine S 84° W 46 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replace Section Corner from two Cedar P.T.'s in good condition.

Corner found by Ken Killmar.

The distance between these P.T.'s was 4 links short so divided the difference, and set Corner accordingly. Corner is 23 links south of 80.00 ch. marker from east.

Corner placed and witnessed January 24, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 2/14/56