

# SURVEY & REMONUMENTATION

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 343 of  
P.A. of 1990 On 5/18/1996

JUL 30 1996

## COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

4-387

Gerald Jackson  
Chairman

FILED  
TIME 3:00 p.m.

For corners in \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Alger (County)

- |   |   |            |   |            |            |
|---|---|------------|---|------------|------------|
| 1. Public Land Survey                   | T | <u>46N</u> | R | <u>18W</u> | <u>M8</u>  |
|   | T |            | R |            |            |
|   | T | <u>46</u>  | R | <u>17</u>  | <u>A-8</u> |
|   | T |            | R |            |            |
| 2. Property Controlling<br>in Section   | S |            | T | R          |            |
|   | S |            | T | R          |            |
| 3. Miscellaneous<br>Property in Section | S |            | T | R          |            |
|   | S |            | T | R          |            |

JUN 27 1996

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on February 08, 1996, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M8: PLS-William A. Burt, D5, 1841, Set qr. section post - Sugar 8", S.49 E., 42 links, Sugar 16", N.20 W., 17 links. No subsequent restoration.\*\*\*\*\* Alger County Road Commission, 1986-1989, Robert L. Jamros, PS, established corner position at single proportionate measurement between existing corners North and South for road alignment purposes prior to the reconstruction and paving of Percy Road.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M8: Found 1/2" Rebar with I.D. cap no. 25849, 1.8 feet East of the centerline of Percy Road, at surface of road. Corner position verified as being established on line and at single proportionate distance between BT Section corner of Sections 13, 24, 18, and 19, T.46N., R.17-18W., and BT Section corner of Sections 25, 36, 30, and 31, T.46N., R.17-18W. Corner position lies in an improved area along Percy Road and all evidence of original BT's has been destroyed. Corner position lines well with dim fence west and northerly edge of open field. Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M8: Set in place of exist. 1/2" rebar a 5/8"x 18" rebar with Berntsen 3 1/4" aluminum cap no. R8D5325, stamped to identify corner position, grouted in place with concrete. Established the following reference trees.\*\* Maple 18", N.66 W., 47.40 feet, PK w/ aluminum I.D. washer.\*\* Maple 18", S.28 W., 111.10 feet, PK w/ aluminum I.D. washer.\*\* Maple 10", N.47 E., 50.77 feet, PK w/ aluminum I.D. washer, Blazed, Painted, Scribed "1/4S BT" and BT signs.\*\* Maple 12", S.38 E., 51.29 feet, PK w/ aluminum I.D. washer, Blazed, Painted, Scribed "1/4S BT" and BT signs. All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 12/25/96

