

SURVEY & REMONUMENTATION

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 245 of
P.A. of 1990 On Feb 19 1999

Mr. Jacki RLS
Chairman

SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-127

For corners in

Alger <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T46N R17W	A 13 ✓	
	T46N R18W	M 13	
	T45N R17W	A 1	
	T45N R18W	M 1	
2. Property Controlling in Section	S ___ T ___ R ___	___	___
	S ___ T ___ R ___	___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___	___
	S ___ T ___ R ___	___	___
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

TIME 10:00 AM.

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on November 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A13: P.L.S. - William A. Burt, DS, 1841. Intersect West township boundary at post, corner of Townships 45 and 46 North, between Ranges 17 and 18 West (post set as temporary in T.45N., R.17W.) * Hemlock 16, N.63°E., 29 links. * Hemlock 20, N.59°W., 54 links. ***** John Burt, DS, 1841. West on the South side of Section 36, T.46N., R.18W., * Hemlock 16, N.63°E., 29 links. * Hemlock 20", N.59°W., 54 links. ***** The following are unrecorded reports from USDA Forest Service Records. ***** L. Lammi, USDA, Forest Service, 1974. Found wood post blazed on 2 sides. 76.38 ch. was written on post with section line brushed North of corner. ***** Glenn A. Bergery, RLS, 1974. * Found wood post at edge of clearing, could not verify. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A13: Located corner position by standard field survey and double proportionate measurement to section corners, 1 mile North 1 mile East, 3 miles South and 4 miles West. Found wooden post of 1974 reports at edge of clearing 60 feet more or less East of corner position, down and decayed. A search was made for original evidence, none remains. Area around corner position appears to be graded, with evidence of dim track roads, dump piles and timber cutting. Monumented corner position as established and made new reference trees. Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A13: Set Berntsen aluminum monument no. AINB30 with 3 1/4" aluminum cap, stamped to identify corner position. Established new reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following. * White Spruce 7", S.48°W., 17.75 feet, "S1 BT"; * Black Spruce 6", N.28°W., 15.09 feet, "S36 BT"; * White Pine 4", N42°E., 17.01 feet, "S31 BT"; * Maple 4", S.53°E., 19.65 feet, "S6 BT". * Survey marker sign on 6 foot steel post, S.24°W., 1.0 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan license No. 25849

Date December 16, 1998

