

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 245 of P.A. of 1990 On 12-10-1997

05-67

Herald W Carlson Chairman

SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 46 R 17 B11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

FILED TIME 8:30 Am

DEC 17 1997

DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Robert L. Jamros, in a field survey on November 04, 1997, 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at row 11, column B.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B11: PLS - William Ives, DS, 1850 * Set quarter section post * Yellow Birch 18, N.28 E., 44 links * Beech 6, S.60 W., 10 links **** D.S.S.&A. Railway Company, Mackinac Division, Right of Way and Track Map, June 30, 1916 * No position shown for quarter section corner **** Michigan State Highway Department Right of Way Maps, 1959-1961 * No position shown for quarter section corner **** No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B11: Established corner position on true line at single proportionate measurement * Position lies in railroad right of way South of main track and siding * Position of corner is at North-South tree line with evidence of old fence wire to South * Monumented corner and established references * Corner position as established is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B11: Set Berntsen Alum. monument no. A1NB20, stamped to identify corner position * Centerline of main track, Wisconsin Central Railroad, North 23.50 feet * Established reference trees w/BI signs, blazed, scribed and painted * Set PK nails w/Alum. I.D. washers for measure in the following - Spruce 6, N.27 E., 55.72 feet, '1/4S BT' * Spruce 8, N.45 W., 84.05 feet, '1/4S BT' * Spruce 6, S.45 W., 49.33 feet, '1/4S BT' * All bearings are magnetic.

Signed by Robert L. Jamros

Date 12/10/1997

Surveyor's Michigan License No. 25849

