

DEC 27 1999

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12-8-1999

Donald W. Kinnunen  
Chairman

For corners in SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

05-180

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 17W	B13 ✓
	T 45N R 17W	B1
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	

FILED  
TIME 1:30 p.m.

DEC 15 1999

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on November 04, 1999, 19\_\_\_\_\_, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, \_\_\_\_\_ recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B13: PLS \* William A. Burt, DS, 1841. \* Set quarter section post. \* Hemlock 10", N.70 E., 10 links. \* Maple 12", N.45 W., 29 links. \*\*\*\*\* No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B13: Located corner search area by calculated position and standard field survey methods. Made search for evidence of GLO corner and accessories, no evidence found. Found flat faced 4" post at N.23 W., 21.5 feet from established corner position, no evident markings. No other evidence to be found around corner position. Established corner position by single proportionate measurement on line between section corners 1/2 mile east and 1/2 mile west. Corner position as monumented is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B13: Set 2 1/2"x30" Berntsen aluminum monument No. A1NB30 with 3 1/4" aluminum cap stamped to identify corner position. \* Established the following reference trees with BT signs, blazed, scribed and painted. \* Set PK nails with aluminum I.D. washers for measure in the following: Maple 10", N.61 E., 14.74 feet, "1/4s BT". \* Maple 8", S.41 E., 22.81 feet, "1/4s BT". \* Hemlock 7", S.41 W., 14.35 feet, "1/4s BT". \* Maple 6", N.75 W., 17.75 feet, "1/4s BT". \* Survey marker sign on 6 foot steel post, S.50 W., 1.3 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date Dec 15 1999

