

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 845 of
P.A. of 1990 On 12-10-1997

05-66

SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____ County) Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>46</u>	<u>17</u>	<u>C2</u>	
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	7	8	9	10	11	12	13	14	15	16	17	18
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Robert L. Tearos, in a field survey on November 16, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C2: PLS - William Ives, DS, 1850 * Set quarter section corner * Sugar B, S.80 E. 39 links * Elm 24, N.67 W., 46 links **** Walter W. Gleason, County Surveyor, 1913 * Set standard iron corner on straight line at proportional distance **** Alger County Road Commission * Van Meer-Shingleton Road * Corner shown at Station 132+54.8 * George L. Depew, Engineer, 1923 **** Munising-Shingleton Road * Corner is shown (no detail) on Constructions Plans, M.S.H.D., 1958 **** Land corner record, M.D. of C. * Monument box, 1 1/2 links West of centerline of M-94 at junction of East-West roads * Billy D. Buckler, RLS, 1960 * No references given * Recorded in Liber 2, Page 199, Alger County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C2: Found 1 inch iron bar in monument box * Identified by description on recorded 1960 report, 1 1/2 links West of centerline of County Road M-15 (old M-94) at East-West road junction * Corner position sets well with record information and distances North and South. Corner position has been accepted and used in area surveys. * Replaced exist. monument and established reference objects * Monument position as found is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C2: Set 5.8 inch by 18 inch Rebar w/Berntsen Alum. cap no. RBD 5325, stamped to identify corner position in exist. monument box * Corner lies 0.30 feet West of centerline of pavement * Established 3 reference trees and the 4th not available, open lawn of residence * Set PK nails w/Alum. I.D. washers in the following - Spruce 14, S.50 W., 56.50 feet * Spruce 20, N.48 W., 57.20 feet * Spruce 20, N.50 E., 51.00 feet * All bearings are magnetic.

Signed by Robert L. Tearos
Surveyor's Michigan License No. 25849

Date 12/10/1997

