

REMONUMENTATION

FEB 19 1998

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-10-1997

SECTION

05-64

Donald W. Kinnunen
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____

Located In: _____

Corner Code # _____

FILED
TIME 2:30 Am

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

1. Public Land Survey	T	46	R	17	C4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jaaros, in a field survey on July 25, 1997, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C4: PLS - William Ives, DS, 1850 * Set quarter section post * Yellow Birch 10, N.93 W., 13 links * Cedar 6, S.64 E., 33 links **** Munising Railway Company, East Branch Extension * R.C. Young, Chief Engineer, 1904 * Quarter corner is shown, but no ties **** Set standard iron corner from original field notes * Walter W. Gleason, County Surveyor, 1913 **** Alger County Road Commission * Van Meer-Shingleton Road * Corner is shown at Station 79+60 * George L. Depew, Engineer, 1923 **** Munising-Shingleton Road * Corner is shown (no detail) on construction plans, M.D.S.H., 1958 **** Land Corner Record, M.D. of C. * Corner lies 5 links West of centerline of M-94 and in line with East-West fences, Billy D. Buckler, 1961, no references given * Alger County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C4: Found 1 inch iron bar in monument box * Identified by description on recorded report, 5 links West of centerline of County Road H-15 (old M-94) in line with East-West fences * Corner position sets well with record information and measured distances North and South * Corner position has been accepted and used in area surveys. * Replaced exist. monument and established reference objects. * Monument position as found is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C4: Replaced 1 inch iron bar with 5/8 inch by 18 inch Rebar w/Berntsen Alum. cap RD 5325, stamped to identify corner position in monument box, 3.3 feet West of centerline of pavement in line with East-West fences * Established reference objects w/BI signs, blazed, scribed and painted * Set PK nails for measuring w/brass I.D. washers in the following - Spruce 10, N.45 E., 136.48 feet, "143 BT" * Red Pine 9, S.74 E., 112.73 feet, "143 BT" * Southeast corner Steel Garage, S.61 W., 118.89 feet * Power Pole, N.19 W., 15.43 feet, "BT" * All bearings are magnetic.

Signed by Robert L. Jaaros
Surveyor's Michigan License No. 25849

Date 12/18/1997

