

**SURVEY &
REMONUMENTATION**

FEB 19 1998

05-63

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-10 1997

Gerald W. Carlson
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>46</u>	R	<u>17</u>	C	<u>5</u>
	T		R			
	T		R			
	T		R			
2. Property Controlling in Section	S		T		R	
	S		T		R	
3. Miscellaneous Property in Section	S		T		R	
	S		T		R	

FILED
TIME 8:30 Am.

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5		4		3		2		1		
3												
4	7	8		9		10		11		12		
5												
6	18	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

I, Robert L. Jamros, in a field survey on July 25, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CS: PLS - William Ives, DS, 1850 * Post set corner of Sections 7, 8, 17 & 18 * Sugar 20, S.34 E., 16 links * Sugar 7, N.18 W., 22 links ***** Munising Railway Company, East Branch Extension * R.C. Young, Chief Engineer, 1904 * Section corner is shown 763 feet East of centerline of railroad at Station 45+60 ***** Set standard iron corner from original field notes * Walter W. Gleason, County Surveyor, 1913 ***** Alger County Road Commission * Van Meer-Shingleton Road, corner shown at Station 53+02.1 * George L. Depew, Engineer, 1923 ***** Munising-Shingleton Road * Corner is shown (no detail) on construction plans, M.S.H.S., 1958 ***** Land Corner Record, M.D. of C. * Monument box lies 1 link East of centerline of M-94 and East-West road junction * No witnesses given * Recorded in Liber 2, Page 192, Alger County Corner Records ***** Robert L. Jamros, RLS, 1980 * Found 1 inch iron bar in monument box, 0.5 feet East of centerline of County Road H-15 (old M-94) * Witnesses - Power Pole, N.43 W., 42.30 feet * Power Pole, S.37 W., 54.10 feet * Power Pole, S.32 E., 48.60 feet * Guy Wire Pole, N.61 E., 52.70 feet * Recorded in Liber 1, Page 398, Alger County Corner Records * No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CS: Found 1 inch iron bar in monument box 0.5 feet East of centerline of pavement of County Road H-15 * Recovered 2 BT's of the 1930 recorded report and established additional references * Corner position measures well to adjacent corners North and South * Distance from corner position to centerline of old railroad grade measures 760 feet * Corner position has been accepted and used in area surveys. * Monument position as found is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

CS: Replaced 1' iron bar with 5/8' by 18' Rebar w/Berntsen Alum. cap RBD 5325, stamped to identify corner position in monument box, 0.5 feet E. of centerline pavement of County Road H-15 * Renewed exist. BT's and established new references w/scribing * Set PK nails w/Alum. I.D. washers in the following - Exist. BT, Power Pole, S.39 W., 53.94 feet, 'BT' * Power Pole, N.41 W., 40.09 feet, 'BT' * Exist. BT, Guy Wire Pole, N.64 E., 52.91 feet, 'BT' * Elm 5, S.38 E., 50.64 feet, 'S 17 BT' * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/10/1997

