

FEB 19 1998

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 318 of
P.A. of 1990 On 12-10-1997

SECTION

05-61

Gerald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located In:	Corner Code #
<u>Alger</u> (County)		
1. Public Land Survey	T <u>46</u> R <u>17</u>	C8
	T <u>46</u> R <u>17</u>	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	

FILED
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on July 25, 1997, 19_____
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C8: PLS - William Ives, CG, 1950 * Set quarter section post * Beech 8, S.32 E., 29 links * Sugar 8, N.8.2 W., 22 links **** George L. Depew, County Surveyor, 1917 * Set standard iron corner, 1 BT found * No references **** Munising-Shingleton Road, corner is shown (no detail) on construction plans, M.D.S.H., 1958 **** Land Corner Record * Michigan Department of Conservation * Billy D. Buckler, 1960 * Corner position in monument box 4 3/4 links West of centerline of M-94 and in line with fence to West * No references given * Recorded in Liber 2, Page 193, Alger County Corner Records **** No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C8: Found 1 inch iron bar in monument box, 3.3 feet West of the centerline of pavement of County Road H-15 (old M-94) * Old fence line evident to West from corner * Corner position measures well to corners North, South and West * Monument box position has been maintained and corner position has been accepted and used in area surveys. * Monument box and corner position are accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C8: Replaced 1 inch iron bar w/5/8 inch by 18 inch Rebar w/Berntsen Alum. cap no. RBD 5325 in exist. monument box, 3.3 feet West of centerline of pavement of County Road H-15 * Established reference trees w/BT signs, blazed and scribed * Set Pa. nails w/Alum. I.D. washers for measure in the following - Maple 9, S.33 E., 56.42 feet, "BT" * Maple 7, S.67 W., 34.68 feet, "BT" * Spruce 7, N.44 E., 32.78 feet, "BT" * White Birch 5, N.23 W., 53.61 feet, no scribing or BT signs * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/10/1997

