

FEB 19 1998

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12-10-1997

SECTION

05-60

Donald W. Kinnunen  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in \_\_\_\_\_

(County)

Located In:

Corner Code #

|                                      |   |           |   |           |           |
|--------------------------------------|---|-----------|---|-----------|-----------|
| 1. Public Land Survey                | T | <u>46</u> | R | <u>17</u> | <u>C9</u> |
|                                      | T | _____     | R | _____     | _____     |
|                                      | T | _____     | R | _____     | _____     |
|                                      | T | _____     | R | _____     | _____     |
| 2. Property Controlling in Section   | S | _____     | T | _____     | R         |
|                                      | S | _____     | T | _____     | R         |
| 3. Miscellaneous Property in Section | S | _____     | T | _____     | R         |
|                                      | S | _____     | T | _____     | R         |

FILED

TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Robert L. Jaaros, in a field survey on November 16, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C9: PLS - William Ives, DS, 1850 \* Set post corner of Sections 19, 20, 29 & 30 \* Sugar 18, S.10 W., 25 links \* Maple 20, N.22 E., 29 links \*\*\*\*\* George L. Depew, County Surveyor, 1917 \* Set standard iron corner \*\*\*\*\* M.S.D.H. Right of Way Maps, Project C-174, 1959-1961 \* Corner position shown North of M-28 survey centerline 4911.38 feet \* Found 2 inch iron pipe w/brass cap \* Witness's - Cherry 14, N.85 W., 22.73 feet \* Cherry 13, S.85 E., 33.79 feet \* Maple 8, S.40 E., 64.50 feet \*\*\*\*\* Land Corner Record, M.D. of C. \* Billy D. Buckler, RLS, 1960 \* Corner position in monument box 1/2 link East of centerline of and in line with fence East \* No references given \* Recorded in Liber 2, Page 194, Alger County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C9: Found 1 inch iron bar in monument box, 0.40 feet East of centerline of pavement of County Road H-15 (old M-94) \* Old fence line evident to East from corner \* Description of monument and accessories of the highway plans of M.S.D.H., 1959-1961, does not relate to this corner position very well, believe that description was originated on corner 1/2 mile South \* North fence line of Cusino Wildlife Station lies West of corner position \* Monument box position has been maintained and the corner position accepted and used in area surveys. \* Measurements to corners North, South and West check well and distance to centerline of M-28 measures 4912.3 feet \* Monument box and corner position are accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C9: Replaced 1 inch iron bar w/5/8 inch by 18 inch Rebar w/Berntsen Alum. cap no. PED 5325, in exist. monument box, 0.40 feet East of centerline of pavement of County Road H-15 \* Established reference trees with BT signs, blazed and scribed \* Set PK nails w/Alum. I.D. washers for measure in the following - Maple 12, S.64 E., 41.64 feet, "BT" \* Maple 10, S.62 W., 53.64 feet, "BT" \* Maple 24, N.25 W., 97.37 feet, no signs or scribing \* Maple Twin 16, N.32 E., 77.25 feet, no signs or scribing \* All bearings are magnetic.

Signed by

Robert L. Jaaros

Date

12/10/1997

Surveyor's Michigan License No.

25849

