

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

5-09

Herold Carlson  
Chairman  
For corners in  
ALGER - SCHOOLCRAFT  
(County)

Located In: Corner Code #

- |                                      |   |     |   |     |     |
|--------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey                | T | 46N | R | 17W | C13 |
|                                      | T | 45N | R | 17W | C1  |
|                                      | T |     | R |     |     |
|                                      | T |     | R |     |     |
| 2. Property Controlling in Section   | S |     | T | R   |     |
|                                      | S |     | T | R   |     |
| 3. Miscellaneous Property in Section | S |     | T | R   |     |
|                                      | S |     | T | R   |     |

FILED  
TIME 2:00 p.m.

MAR 31 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY MI  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

T.45N R.17W. C1 Schoolcraft Co

I, Robert L. Jaaros, in a field survey on April 09, 1996, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C13: PLS - William A. Burt, DS, 1841, Set post corner of Sections 31 & 32 \* Maple 7, N.31 E., 22 links \* Beech 8, N.56 W., 34 links \*\*\*\*\* Dean C. DeLamater, RLS, 1-21-1954. \* Michigan Dept. of Conservation Forestry Division. \* This corner was found by Forestry Division survey crew, while making a partial resurvey of this area. One original B.T. still in place, in poor condition. Corner was placed and witnessed May 26, 1953. \* Set 1" Pipe with 4" Brass cap.\* Witness, 12' S. Maple, S.58 E., 42 links. \* 8' S. Maple, S.62 W., 26 links. \* Recorded in L.2, P.50, Alger County Records.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C13: Found 1" Iron Pipe w/ 4" Brass cap stamped to identify corner position with 4" Squared top scribed post. Reference trees of the 1954 report are damaged and /or dead. Established four new reference trees. Monument found at corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

**SURVEY & REMONUMENTATION**


AUG 15 1997

COMMISSION

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C13: Stamped P.A. 345 in existing Brass capped monument. Established reference trees with BT signs, Blazed, scribed and painted. Set PK nails w/ aluminum I.D. washers for measure. \* Maple 16", N.28 E., 52.89 feet, "S32 BT". \* Maple 12", S.16 E., 25.98 feet, "S5 BT". \* Balsam 7", N.87 W., 50.80 feet, "S31 BT". \* Maple 10", S.35 W., 52.12 feet, "S6 BT". \* Survey marker sign on six foot steel post, S.32 E., 0.90 feet. \* All bearings are magnetic.

Signed by Robert L. Jaaros  
Surveyor's Michigan License No. 25849



Date 25 March, 1997