

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12-8-1999

Donald W. Kinnunen  
Chairman

DEC 27 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alger SECTION  
(County)

Located In:

Corner Code #

05-181

- |                                    |   |     |   |     |    |
|------------------------------------|---|-----|---|-----|----|
| 1. Public Land Survey              | T | 46N | R | 17W | D2 |
|                                    | T |     | R |     |    |
|                                    | T |     | R |     |    |
|                                    | T |     | R |     |    |
| 2. Property Controlling in Section | S |     | T |     | R  |
|                                    | S |     | T |     | R  |
| 3. Miscellaneous                   | S |     | T |     | R  |
| Property in Section                | S |     | T |     | R  |

FILED  
TIME 1:30 p.m.

DEC 15 1999

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on October 12, 1999, 19\_\_\_\_\_, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D2: Center of Section 5. \* George L. Depew, CS, 1919. \* Set iron corner. \* Established center post at intersection of N-S and E-W centerlines. \* No references given. \* Book 7, Alger County Road Commission, Alger County Records. \*\*\*\* Robert L. Jamros, RLS, 1988. \* Found remains of Alger County Standard Monument, steel base plate with 2" hole, 4 feet below surface of gravel road. \* Set 1/2"x18" rebar with RLS cap. \* Power pole, North, 26.6 feet. \* R.Pine 8", S.61 E., 75.4 feet. \* Telephone pedestal, N.41 E., 40.0 feet. \* Liber 3, Page 349, Alger County Corner Records. \*\*\*\* No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D2: Located corner monument with existing references of the report of 1988. Found 1/2" rebar with RLS cap on centerline of gravel road and in good condition. Corner position lies 2.35 feet west and 1.51 feet south of the actual intersection of N-S and E-W centerlines. Replaced with a new monument and renewed and/or established references. Corner monument as found and renonumented is accepted as the best available evidence of the corner position established by George L. Depew, CS, 1919.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D2: Set 5/8"x18" rebar with a Berntsen 3 1/4" aluminum cap No. RBD5325 in place of existing 1/2" rebar. \* Stamped monument cap to identify corner position. \* Renewed existing references and added an additional one. \* Set PK nails with aluminum I.D. washers for measure in the following that are applicable: Power pole, N.05 E., 26.63 feet. \* R.Pine 18", S.60 E., 75.53 feet. \* J.Pine 8", S.67 W., 98.45 feet. \* Telephone pedestal, N.45 E., 40.0 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date Dec 15 1999

