

DEC 27 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-8-1999

Gerald Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Alger

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 46N R 17W D5
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Robert L. Jamros, in a field survey on April 20, 1999, 19_____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, _____ recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D5: PLS * William Ives, DS, 1850. * Set quarter section post. * Hemlock 12", S.61 W., 03 links. * Cedar 6", N67 E., 14 links. ***** George L. Depew, CS, 1917. * Set iron corner from Government field notes. * No references set. * Recorded in the Minutes of County Surveys, Alger County Records. ***** No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D5: Located corner search area by calculated position and standard field survey methods. Found 2" iron pipe with brass cap stamped to identify corner position, dated November 7, 1917. Monument in good condition. * Also found 3 existing BT's, blazed and scribed, author unknown. * Corner monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D5: Existing 2" iron pipe with 3 1/4" brass cap. * Renewed existing reference trees with BT signs and paint. * Established an additional reference tree with BT signs, blazed, scribed and painted. * Set PK nails with aluminum I.D. washers for measure in the following: Existing - Y.Birch 10", N.29 W., 27.47 feet (S8 BT). * Existing - Maple 10", S.66 W., 20.03 feet (S17 BT). * Existing Maple 7", S.18 E., 45.65 feet (S17 BT). * Maple 11", N.49 E., 52.08 feet, "1/4s BT". * Survey marker sign on 6 foot steel post, N.61 W., 1.0 feet. * All bearings are magnetic.

FILED 05-183
TIME 1:30 p.m.

DEC 15 1999
DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5			●									
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Signed by Robert L. Jamros
Surveyor's Michigan License No. 75849

Date Dec 13, 1999

