

DEC 27 1999

Approved by Alger County
Land Survey Re-monumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-8-99

Harold Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>17W</u>	<u>E2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

05-185

FILED
TIME 1:30 p.m.

DEC 17 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5	4			3		2			
3													
4	7			8	9			10		11			12
5													
6	18			17	16			15		14			13
7													
8	19			20	21			22		23			24
9													
10	30			29	28			27		26			25
11													
12	31			32	33			34		35			36
13													

I, Robert L. Jamros, in a field survey on April 16, 1999, 19_____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, _____ recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E2: PLS * William Ives, DS, 1850. * Set quarter section post. * Sugar 22", N.32 W., 30 links. * Sugar 18", S.39 E., 28 links. **** George L. Depew, CS, 1919. * Set iron corner from government notes as part of a section subdivision survey of Section 5, T.46N., R.17W., April 3, 1919. * No references given. * Recorded in Book 7, Alger County Road Commission, Alger County Records. **** No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Located corner search area by calculated position and standard field survey methods. Found 2" iron pipe with 3 1/4" brass cap, unstamped. No GLO evidence found. The survey of George L. Depew, DS, 1919, reports a distance of 2662 feet for the South 1/2 mile and 2641 feet for the North 1/2 mile. Distances measured as part of this corner recovery are 2661.32 feet and 2638.04 feet, respectively. The GLO distances of 1850 are 2651.9 feet and 2630.1 feet, respectively. The existing corner monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E2: Existing 2" galvanized iron pipe with 3 1/4" brass cap. * Stamped identification on top of brass cap. * The following reference trees were established, blazed, scribed, BT signs, and paint. * PK nails with aluminum I.D. washers for measure set in the following: Maple 18", S.38 W., 7.20 feet, "1/4s BT". * Maple 5", N.39 W., 15.84 feet, "1/4s BT". * Maple 8", N.51 E., 22.24 feet, "1/4s BT". * Maple 15", S.40 E., 13.53 feet, "1/4s BT". * Survey marker sign on 6 foot steel post, S.64 E., 1.5 feet. * All bearings are magnetic.

Signed by Robert L. Jamros Date Dec 13, 1999
Surveyor's Michigan License No. 25849

