

**SURVEY &
REMONUMENTATION**

FEB 23 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-131

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16/1998

Michael Davis
Chairman

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R17W	<u>E 13</u> ✓
	T45N R17W	<u>E 1</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

TIME 10:00 Am.

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on November 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E13: P.L.S. - William A. Burt, DS, 1841. * Set post corner of Sections 32 and 33. * W. Pine 14, N.67°E., 99 links. * Cedar 8, N.9°W., 7 links. ***** William Ives, DS, 1850. Section corner on North boundary of T.45N., R.17W. * Cedar 8, S.10°W., 10 links; * Tamarack 12, S.41°E., 22 links. ***** Billy D. Buckler, RLS, 1957. * Replaced section corner from Tamarack B.T. in fair condition. Corner found while making a partial re-survey of this area. * Set 1" iron pipe with brass cap. * 7" Cedar (S4 NBT), S.78°E., 54 links; 7" Cedar (S5 NBT), S.49°W., 43 links. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E13: Located corner position by standard field survey and single proportionate distance from 2 corners to the West. Found 1" G.I.P. with brass cap and 1 reference tree, 7" Cedar, S.78°E., 54 links. No original evidence remains. Established new reference trees. Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E13: Existing monument, 1" G.I.P. with 4 inch brass cap. Renewed 1 existing reference tree with BT signs and paint. Established new reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following. * Existing - Cedar 11", S.70°E., 35.29 feet, scribing visible; * Cedar 8", S.20°W., 9.90 feet, "S5 BT"; * Cedar 7", N.36°W., 19.33 feet, "S32 BT"; * Cedar 6", N.28°E., 13.50 feet, "S33 BT". * Survey marker sign on 6 foot steel post, S.20°W., 0.5 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

