

SURVEY & REMONUMENTATION

FEB 23 1999

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 345 of P.A. of 1990 On 12/16/1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-132

Chairman

For corners in

Form with fields for Alger (County), Located In: T46N R17W, Corner Code # F 11, and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

TIME 10:00 A.M.

JAN 8 1999

DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is present at the intersection of column F and row 11.

I, Robert L. Jamros, in a field survey on December 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F11 P.L.S. - William Ives, DS, 1850. \* Set quarter section post. \* Cedar 8, N.51°E., 6 links. \* Tamarack 8, S.13°W., 20 links. \*\*\*\*\* Right of Way and Track Map, D.S.S.&A. Railway Company, Mackinaw Division, June 30, 1916. \* No corner or track station shown. \* Alger County Road Commission Records, File 16-2. \*\*\*\*\* Michigan Department of Transportation, Projects, Seney-Munising Road, and Highway M-28, 1948 to present. \* No corner shown. North-South quarter line station shown as approximate, 499+02. \* Alger County Road Commission Records File 10-1. \*\*\*\*\* No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F11: Located corner position by standard field survey and single proportionate measurement on line and between section corners East and West. \* No original evidence remains. \* Monumented the corner position as established and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F11: Set Berntsen aluminum monument no. AINB30 with 3 1/4" aluminum cap, stamped to identify corner position. Established reference trees with BT signs, blazed and scribed. Set PK nails for measure with aluminum I.D. washers in the following. \* White Spruce 7", N.55°W., 9.96 feet, "1/4S BT"; \* White Pine 5", N.68°E., 23.59 feet, "1/4S BT"; \* Jack Pine 6", S.75°E., 14.51 feet, "1/4S BT"; \* Spruce 5", S.79°W., 22.80 feet, "1/4S BT"; \* Centerline of pavement on Highway M-28, North, 113.5 feet; \* North face of North rail, Wisconsin Central Railroad, South, 32.88 feet. \* Survey marker sign on 6 foot steel post, N.85°W., 1.0 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros Surveyor's Michigan License No. 25849

Date December 16, 1998

