

**SURVEY &
REMONUMENTATION**

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-135

For corners in

<u>Alger</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>17W</u>	<u>111</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

TIME 10:00 AM

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on November 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

111: P.L.S. - William Ives, DS, 1850. * Section corner post set, 26, 27, 34 and 35. * Cedar 12, S.34°W., 13 links. * Cedar 8, N.60°E., 49 links. ***** Right of Way and Track Map, D.S.S.&A. Railway Company, Mackinaw Division, June 30, 1916. * Section corner shown at Station 5369+40 and 68 feet North of centerline of tracks. No corner material implied or references given. * Alger County Road Commission Records, File 16-2. ***** Michigan Department of Transportation, Projects, Seney-Munising Road, and Highway M-28, 1948 to present. * No corner shown, approximate section line Station, 578+73. * Alger County Road Commission Records, File 10-1. * No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

111: Located corner position by standard field survey and single proportionate measurement between existing corners 1 mile East and 3 miles West. * North-South corner position established at 68 feet North of centerline of existing railroad rails. * No original evidence remains. * Monumented corner position as established, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

111: Set Berntsen aluminum monument no. AINB30 with 3 1/4" aluminum cap, stamped to identify corner position. Established new reference trees with BT signs, blazed and scribed. Set PK nails for measure with aluminum I.D. washers in the following: * Tamarack 3", S.10°W., 21.09 feet, "BT"; * Tamarack 6", with old blaze scar facing corner position, N.83°E., 4.53 feet, "BT"; * Twin Tamarack 7"-10", N.76°W., 13.16 feet, "BT"; * Spruce 3", S.89°W., 20.90 feet, "BT"; * Centerline of pavement on Highway M-28, North, 81.8 feet. * North face of North rail, Wisconsin Central Railroad, South 65.48 feet. * Survey marker sign on 6 foot steel post, S.72°W., 0.80 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

