

**SURVEY &  
REMONUMENTATION**

FEB 23 1999

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12/16 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

05-137

McAnn RLS  
Chairman

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>R17W</u>	<u>K 11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

TIME 10:00 AM.

JAN 8 1999

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on November 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

**K11:** P.L.S. - William Ives, DS, 1850. \* Post set corner of Sections 25, 26, 35 and 36. \* Cedar 12, N.31°E., 24 links. Cedar 24, S.40°W., 28 links. \*\*\*\*\* Right of Way and Track Map, D.S.S.&A. Railway Company, Mackinaw Division, June 30, 1916. \* Section corner shown at Station 5316+61 and 76 feet North of centerline of tracks. No corner material implied or references given. \* Alger County Road Commission Records, File 16-2. \*\*\*\*\* Michigan Department of Transportation, Projects, Seney-Munising Road and Highway M-28, 1948 to present. \* Corner shown at Station 631+78.57 as 4" Cedar hub on railroad right of way, 94.54 feet South of centerline of highway right of way, no witnesses given. \* Alger County Road Commission Records, File 10-1. \*\*\*\*\* Gerald W. Carlson. RLS, 1980. \* C.C.I Records indicate old post 94 links North of North rail of D.S.S.&A. Railroad. \* Set 5/8" x 18" iron with RLS cap, 94 links North of North rail of D.S.S.&A. Railroad at centerline of road to North, 73 feet South of centerline of M-28. \* Witnesses, 4" Aspen, N.71°W., 17.78 feet; \* 2" Spruce, N.31°W., 6.51 feet; Power Pole, N.55°E., 21.04 feet; \* Railroad marker post, N.40°E., 2.35 feet. \* Liber 1, Page 275, Alger County Corner Records. \*\*\*\*\* No other record of restoration.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**K11:** Located corner position by standard field survey. Found 5/8" iron with cap no. 24589, Gerald W. Carlson. \* Located witnesses of 1980 report, in good condition. \* Corner position lies 94 links North of North rail of D.S.S.&A. Railroad (now Wisconsin Central Railroad) and on centerline of road to North. \* 5/8" iron as found is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**K11:** Installed Bernsten aluminum monument no. AINB30 with 3 1/4" aluminum cap over existing iron, stamped to identify corner position. Renewed existing references with BT signs. \* Established a new reference tree with BT signs, blazed and scribed. \* Set PK nails for measure with aluminum I.D. washers in the following \* Existing - Aspen 7", N.67°W., 17.75 feet; \* Existing - Spruce 5", N.27°W., 6.51 feet; \* Existing - Marker Post, N.53°E., 2.40 feet; \* Balsam 6", N.58°E., 8.34 feet, \*BT\*. \* Centerline of pavement on Highway M-28, North, 83.1 feet; \* North face of North rail, Wisconsin Central Railroad, South, 61.95 feet. \* Survey marker sign on 6 foot steel post, S.70°W., 0.9 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date December 16, 1998

