

**SURVEY &
REMONUMENTATION**

FEB 23 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

05-138

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16 1998
Robert L. Jamros
Chairman

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>17W</u>	<u>L 11</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

TIME 10:00 AM

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on November 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L11: P.L.S. - William Ives, DS, 1850. * Set quarter section post. * Cedar 10, N.75°E., 44 links. * Cedar 14, S.69°W., 14 links. ***** Right of Way and Track Map, D.S.S.&A. Railway Company, Mackinaw Division, June 30, 1916. * No corner or track station shown. * Alger County Road Commission Records, File 16-2. ***** Michgian Department of Transportation, Projects, Sney-Munising Road, and Highway M-28, 1948 to present. * No corner shown. North-South quarter line station shown as approximate, 658+35. * Alger County Road Commission Records, File 10-1. ***** Gerald W. Carlson, RLS, 1980. * Set 5/8" x 18" iron with RLS cap, Equidistant on line, 76 feet South of centerline of M-28, 68.55 feet North of North rail of D.S.S.&A. Railroad. * Witnesses, 2" Cedar, S.83°E., 19.32 feet; * 2" Spruce, S.40°E., 29.16 feet; * 2" Cedar, S.05°E., 32.68 feet; * 2" Spruce, S.37°W., 2.62 feet. * Liber 1, Page 275, Alger County Corner Records. * No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L11: Located corner position by standard field survey and single proportionate measurement. Found 5/8" iron with cap no. 24589, Gerald W. Carlson, RLS, and in acceptable position. Found reference trees of the 1980 report in good condition. Corner monument as found is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L11: Set Berntsen aluminum monument no. AINB30 with 3 1/4" aluminum cap over existing 5/8" iron, stamped to identify corner position. Renewed existing reference trees with BT signs. Set PK nails for measure with aluminum I.D. washers in the following * Existing - Cedar 4", S.79°E., 19.31 feet; * Existing - Spruce 3", S.36°E., 32.74 feet; * Existing - Cedar 2", S.04°E., 29.22 feet; * Existing - Spruce 5", S.39°W., 2.77 feet; * Centerline of pavement on Highway M-28, North, 75.2 feet; * North face of North rail, Wisconsin Central Railroad, South 68.41 feet. * Survey marker sign on 6 foot steel post, S.33°E., 1.70 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

