

**SURVEY &
REMONUMENTATION**

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16/1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-139

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T46N R17W	<u>M 11</u> ✓	
	T46N R16W	A 11	
	T ___ R ___	___	___
	T ___ R ___	___	___
2. Property Controlling in Section	S ___ T ___ R ___	___	___
	S ___ T ___ R ___	___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___	___
	S ___ T ___ R ___	___	___
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

TIME 10:00 AM

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on November 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M11: P.L.S. - William A. Burt, DS, 1841. * Set post corner of Sections 25 and 36. * Tamarack 3, S.57°E., 60 links. * Tamarack 4", N.27°W., 50 links. ***** Right of Way and Track Map, D.S.S.&A. Railway Company, Mackinaw Division, June 30, 1916. * Section corner shown at approx. Station 5262+86 and North of centerline of tracks. * No corner material implied or references given. * Alger County Road Commission Records, File 16-2. ***** Michigan Department of Transportation, Projects, Seney-Munising Road, and Highway M-28, 1948 to present. * No corner shown, section line Station, 685+29.79. * Alger County Road Commission Records, File 10-1. ***** Billy D. Buckler, RLS, 1962. * 2" iron pipe with 4" brass cap. * This corner was recorded as set by M.S.H.D. * Placed and witnessed September 19, 1961. * Power Pole, S.66°W., 56.10 feet * White Post 2.0 feet North of corner. * Unrecorded ***** Gerald W. Carlson, RLS, 1980. * Found 1" pipe with brass cap, Department of Conservation, 70.7 feet South of centerline of M-28. * Witnesses, Wood Post, N.03°E., 1.85 feet; * Railroad Marker Post, S.03°W., 10.82 feet; * 3" Square Post, N.75°W., 14.60 feet; * 3" Square Post, N.56°W., 17.65 feet. * Liber 1, Page 275, Alger County Corner Records. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M11: Located corner position by standard field survey. Found 2 1/2" G.I.P. with brass cap and witnesses of the 1980 report in good condition, witnesses support monument position. Brass cap (4"), inscribed State of Michigan, unstamped. Corner position lies 70.3 feet South of the centerline of M-28. * Section corner monument 1 mile East, measures 5026.54 feet, GLO record is 5029.2 feet. * No original evidence remains. * Existing monument as found is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M11: Existing 2 1/2" G.I.P. with brass cap, stamped to identify corner position (November 15, 1998). * Established 2 new reference trees with BT signs, blazed and scribed. Set PK nails for measure with aluminum I.D. washers in the following. * Tamarack 8", S.54°W., 10.90 feet, "BT"; * Tamarack 10", N.77°W., 59.93 feet, "BT"; * Existing - Wood Post 6", N.08°E., 1.85 feet; * Existing - Railroad Marker Post 7", S.05°W., 10.85 feet. * Centerline of pavement on Highway M-28, North, 70.3 feet; * North face of North rail of Wisconsin Central Railroad, South, 74.89 feet. * Survey marker sign on 6 foot steel post, S.36°W., 2.0 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

