

Lausing

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alger

Form with fields for (County), Located In, Corner Code, and numbered items 1-5 describing survey types and section information.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Aug 29 2001

I, Stephan J. Szyszkoski, in a field survey on, 19, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and a dot in cell C11.

A. Description of original monument and accessories and/or subsequent restoration:

West 1/16 corner between Sections 29 and 32. Corner established by the undersigned 19 Sept. 2000 and filed in the Alger County Record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Reference monuments of record have been destroyed by unknown persons. Perpetuated the position of record by making new references and witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner position not monumented.
1"x36" Iron pipe with 4" MDNR cap in concrete at S45E 25.00'
1"x36" Iron pipe with 4" MDNR cap in concrete at S45W 25.00'
1"x36" Iron pipe South 25.0'
1"x36" Iron pipe North 15.0'

PK nail in RR tie NE 0.5'
Center of RR switch S49W 13.85'
Center of metal post for sign "N", N86E 60.15'
Brgs magnetic. Distances are horizontal.



Signed by [Signature] Date 1/15/02
Surveyor's Michigan License No. 33986