

Lausing

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Schoelerstaff Alger (County)

Located In: Corner Code #

- 1. Public Land Survey T R
2. Property Controlling in Section S 31 T 46N R 17W 2 S 31 T 46N R 17W 6
3. Miscellaneous Property in Sec. S T R S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and two dots in row 11.

Aug 29 2001

I, Stephan J. Szyszkoski, in a field survey on 19, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (2-Sec. 31) East 1/16 corner between Sections 30 and 31. Not established in the original survey.
(6-Sec. 31) Northeast 1/16 corner Section 31. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing-corner:

- (2-Sec. 31) Established the corner midway and on line between Section corner 1319.22' easterly and Quarter corner 1319.22' westerly (mean true bearing of line is S89 deg. 53' 57"E).
(6-Sec. 31) Established the corner at the intersection of straight lines connecting opposite 1/16 corners computed by regular subdivision of this section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (2) Set 1"IDx36" Iron pipe w/plastic cap "MICH DNR PS33986". Blazed, scribed, and set measuring nails with tags in:
7" W.Pine N46E 58.15' "E1/16 BT"
5" W.Pine N20E 59.5' do
6" W.Pine N25W 79.3' do
Power Pole N10E 67.2'
C/L of RR siding is north 0.25'. C/L of main line RR is north 14.7'. Brgs magnetic, Dist. to nail with tag.
(6) Set 1"IDx36" iron pipe with 4" alum. MDMR cap. Blazed, scribed, and set measuring nails in:
5" Spruce S48W 5.75' "NE1/16 BT"
6" Spruce S83W 6.9' do
5" Balsam N13E 26.7' do
6" Balsam N28E 24.25' do
Cedar post adjacent. Bearings are magnetic. Distances to nail with tag.



Signed by [Signature] Date 1/15/02
Surveyor's Michigan License No. 33986