

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Alger  
 \_\_\_\_\_  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                    |   |     |   |     |    |
|------------------------------------|---|-----|---|-----|----|
| 1. Public Land Survey              | T | 46N | R | 17W | E6 |
|                                    | T |     | R |     |    |
|                                    | T |     | R |     |    |
|                                    | T |     | R |     |    |
| 2. Property Controlling in Section | S |     | T | R   |    |
|                                    | S |     | T | R   |    |
| 3. Miscellaneous                   | S |     | T | R   |    |
| Property in Sec.                   | S |     | T | R   |    |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sep 04 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17	●	16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(E6) Quarter corner common to Sections 16-17. 1953: Remonumented in the probable original position by Michigan Dept. of Conservation. 1" Pipe with 4" brass cap. 8" Cedar N74W 24 links, 9" Cedar N62E 30 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(E6) Recovered the 1953 monument as described, in good condition, and at record bearing and distance from the 1953 accessories, both in good condition with overgrown blazes. Made new top blazes on the 1953 cedars. Found no evidence of the probable OBT noted in the 1953 record.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(E6) Found 1" ID iron pipe with 4" MI Dept. of Conservation tablet. Blazed, scribed, and set measuring nails in:  
 12" Cedar N73W 16.5' "1/4S"  
 12" Cedar N68E 21.4' do  
 6" Cedar N85E 17.6' "1/4S NBT"  
 6" Cedar S20E 14.25' do  
 Bearings are magnetic. Distances to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/08/01

For the Michigan Department of Natural Resources - Office of Property Management