

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alger	Located In:	Corner Code #	
<small>(County)</small>			
1. Public Land Survey	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S <u>17</u> T <u>46N</u> R <u>17W</u>	_____	8
	S <u>17</u> T <u>46N</u> R <u>17W</u>	_____	10
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 03 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (8-Sec. 17) West 1/16 corner, Section 17. Not established in the original survey.
 (10-Sec. 17) South 1/16 corner between Section 17 and 18. Corner monumented at an erroneous position by Billy D. Buckler in 1981.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 17) Established the corner midway and on a straight line between Quarter corner 1325.77' west and the unmonumented Center of Section, being the intersection of 1/4 lines, 1325.77' east.
 (10-Sec. 17) Established the corner midway and on a line of mean true bearing between Quarter corner 1323.59' north and Section corner 1323.59' south. The corner falls 2.5' west of the Centerline of County Rd. H17. The "T" iron placed by Buckler in 1981 was recovered S22E, 15.03' distant, and was not accepted as marking the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1" IDx36" iron pipe with 4" alum. HDNR cap. Blazed, scribed, and set measuring nails in:	(10) Set 1" IDx36" iron pipe with plastic cap #33986.
5" W. Birch N10W 2.5'	Power Pole S44W 32.55' nail & tag.
8" W. Birch N76E 1.65'	USGS monument with brass cap S22E 71.4'
10" Cherry N40W 12.65'	Fd. "T" iron S22E 15.03'
8" Maple N85W 4.5'	10" Maple S40W 90.65' nail & tag
Center of N-S trail is 22' east. Set cedar fence post adjacent. Bearings are magnetic. Distances to nail with tag.	C/L trail to east is approx 36' south. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/08/01
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Office of Property Management