

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alger</u>	Located In:	Corner Code #	
<small>(County)</small>			
1. Public Land Survey	T <u> </u> R <u> </u>		
	T <u> </u> R <u> </u>		
	T <u> </u> R <u> </u>		
	T <u> </u> R <u> </u>		
2. Property Controlling in Section	S <u>17</u> T <u>46NR 17W</u>		<u>1</u>
	S <u>17</u> T <u>46NR 17W</u>		<u>11</u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>		
	S <u> </u> T <u> </u> R <u> </u>		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 03 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5				●									
6		10		17		16		15		14		13	
7				●									
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (1-Sec. 17) West 1/16 corner between Sections 8 and 17. Not established in the original survey.
 (11-Sec. 17) Southwest 1/16 corner, Section 17. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 17) Established the corner midway and on a line of mean true bearing between Section corner 1326.59' west and Quarter corner 1326.59' east. The corner falls in the center of a road to the west and in the easterly side of a trail to the southeast.
 (11-Sec. 17) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The corner falls on the east side of a trail road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 1" IDx36" iron pipe with plastic cap #33986, buried. Blazed, scribed, and set measuring nails in:	(11) Set 1" IDx36" iron pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
6" Spruce N50W 40.5' "W1/16 BT"	5" Beech N58E 2.15' "SW1/16 BT"
6" Balsam S76E 36.5' do	5" Maple S20E 6.8' do
24" Spruce S20E 77.9' do	10" Maple S43W 29.3' do
24" Spruce S03W 50.75' do	12" W. Birch N70W 38.75' do
Bearings are magnetic. Distances to nail with tag.	Set cedar fence post adjacent. Bearings are magnetic. Distances to nail with tag.



Signed by Stephan J. Szyszkoski Date 11/08/01
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Office of Property Management