

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alger

(County)

Located in:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling
 in Section

S 26 T 46W R 17W 6
 S 26 T 46W R 17W 12

3. Miscellaneous
 Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

12 Oct 02 2002
 6 Oct 03 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (6-Sec. 26) Northeast 1/16 corner. Not established in the original survey.
 (12-Sec. 26) South 1/16 corner. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (6-Sec. 26) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (12-Sec. 26) Established the corner midway and on a straight line between Quarter corner 1319.29' South and Center of Section 1319.29' North. The Center of Section was left unmonumented in this survey. The corner falls in an old overgrowing skid trail.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 5" Spruce N08E 58.8' "NE1/16 BT" 8" Spruce N45E 32.65' do 4" Spruce N54E 1.7' do 14" W.Pine S79W 17.55' do Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 14" Spruce S08W 21.25' "S1/16 BT" 10" Spruce S86W 49.6' do 10" W.Birch N04E 32.85' do 12" Spruce East 52.15' do Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/5/02