

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Alger COUNTY


T 46 N R 22 W

DESCRIPTION OF CORNER 1/4 corner for sections $\frac{9}{16}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11/13/69, F. J. Bray with B. McDonald

WITNESSES TO CORNER..... 18" Cedar (1/4 S) (NBT) N 59° E, 41½ links



12" Cedar (1/4 S) (NBT) S 30° W, 41 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between section corners to east and to west. Corner checks fairly well with stream crossing to west. Stream lies in flat low land, course of which may have changed.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

12/10/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68