

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Alger COUNTY


T 46 N R 22 W

DESCRIPTION OF CORNER Section corner for sections ^{9/10} 16/15

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/9/69, F. J. Bray

WITNESSES TO CORNER..... 9" H. Maple (S.9) (NBT) N 22° W, 11 links



10" H. Maple (S.16) (NBT) S 21° W, 41½ links

Possible original B.T., S 40° W, 11 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced at wood post with point of older post along side.
Chopped out faces on H. maple to SW which checks with bearing and distance
for B.T. in original notes.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE 12/11/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68