

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4 - 223

Gerald W. Carlson
Chairman
For corners in
Alger
(County)

Located In: Corner Code #

- 1. Public Land Survey T 46N R 18W A3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

**SURVEY &
REMONUMENTATION**

MAY 16 1995

COMMISSION

Recorded June 24, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Corner Rec.
on Page 223

Don W. Kimmner
Alger County Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on July 15, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A3: P.L.S., John Burt, DS, 1841. Set post corner of Sections 1 & 12. Beech 12, S.43 E., 41. Beech 12, N.49 W., 48. Corner shown on Alger County R.C. Alignment drawings for existing road, noted as "iron", Mid 1930's. John R. Radcliffe, RLS, 1973, found 1" rod and recorded in corner record No. 50, A.C. Records. Herbert L. Fluharty, RLS, 1976, found 1" iron, est. references, 18' Beech, S.08 E., 52.53. 12" Maple, North, 46.85. Power Pole, N.75 E., 36.65, and recorded in corner record No. 88 A.C. Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A3: Found 1 inch Iron Bar, identified by recorded reference objects, 17 feet North of Centerline of asphalt road. Installed monument over existing 1 inch Iron bar, with top 4 inches below ground level. Established additional new references, and is accepted as the best available evidence of the position of the original corner. Corner also lies 20 feet West of centerline of existing driveway.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A3: Set 2 1/4" x 30" Aluminum monument w/3 1/4" Aluminum cap stamped to I.D. Corner position over exist 1 inch iron bar. Set 4" below grade. Est. reference trees blazed and scribed. Set PK nails for measuring w/brass I.D. washers in the following reference trees. 5" steel well casing, N.50 W., 72.71 feet. Exist - Maple 16', North, 46.93 feet, "BT". Power Pole #610, N.75 E., 36.53 feet, "BT". Beech 20", S.08 E., 52.64 feet, "BT".

Signed by Robert L. Jamros Date 1 June, 1994
Surveyor's Michigan License No. 25849