

Merald W Carlson  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

4-224

For corners in

Alger	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 46N R 18W	A4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded June 24, 1994  
at 8:00 o'clock A. M., and  
Recorded in Liber 4 of Corner Rec  
on Page 224

Merald W Carlson  
Alger County Register of Deeds

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on August 25, 1993, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A4: P.L.S., John Burt, DS, 1841. Set quarter Section post. Beech 12, S.57 E., 26. Beech 12, N.17 W., 29. L.E. Adams, C.S., September 1912. Set iron monument from Government field notes as part of subdivision of Section 12, T49N R19W. Herbert L. Fluharty, RLS, 1975, Set 5/8" x 18" re-rod w/RLS cap at extension of line from center of Section and 1/8 corner as part of survey in Section 12, T46N, R19W. Established references, 8" Maple, S.25 E., 30.33 feet, 16" Maple, N.45 E., 20.72 feet, 9" Maple, N.13 W., 29.98 feet. Recorded in corner record No. 71 A.C. Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A4: Found 5/8" rebar badly bent with RLS cap missing, identified by recorded reference objects. Made search for original BT's. BT in Southeast position claimed by road construction. At location of BT in Northwest position found badly decayed wood in stump hole, could not identify species. Installed new 5/8" x 18" rebar with 3 1/4" Aluminum cap, of which top is 12" below road surface. Corner position is 9 feet North of centerline of gravel road and 2 feet east of N-S fence and is accepted as the best available evidence of the position of the original corner. Renewed existing references and added additional references and Survey Marker sign.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A4: Set 5/8" x 18" rebar w/3 1/4" Alum. cap stamped to I.D. corner position. Renewed existing and Est. new reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. in the following reference trees. Exist - Maple 22", N.43 E., 20.85 feet, "1/4S". Exist - Transformer Power Pole, S.11 W., 29.09 feet, "BT". Exist - Tri-Maple 6"-7"-9", N.12 W., 29.97 feet, "BT". Maple 6", S.27 E., 35.13 feet, "1/4S-BT". Sur. Marker sign.

Signed by Robert L. Jamros Date 1 June, 1994  
Surveyor's Michigan License No. 25849