

Merrill W. Carlsson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-225

For corners in
Alger

(County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>46N</u> R <u>18W</u>	<u>83</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded June 24, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Corner Rec
on Page 225

D. W. Kinnaman
Alger County Register of Deeds

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on July 15, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3	●												
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

83: P.L.S., George E. Adair, DS, 1855. Set qr. Section post. Beech 9, N.41 E., 25 links. Beech 8, S.13 1/2 W., 25 links. Corner shown on Alger County R.C. Alignment drawings for existing road, noted as "Iron", Mid 1930's. C.C.I. Co., Forestry Division, on Land & Timber Examination Report as "Iron Pipe", 1946 through 1968. Shown as existing corner, and P.O.B. on the plat of R & M Estates, Liber 1, Page 61, A.C.R., Monument material not given. John R. Radcliffe, RLS, 1973, Found 2" pipe and established references, 16" Maple, N.10 W., 53.93 feet, 10" Maple, S.15 E., 31.38 feet, 12" Maple, S.30 E., 35.08 feet., and recorded in corner record No. 50, A.C. Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

83: Found 1/2 inch rebar and identified by recorded reference objects, 2 feet North of centerline of asphalt road extended east and 11 feet north of north edge of asphalt drive. Two inch pipe has been replaced by this 1/2" rebar. Measurements from existing BT's give location at 1/2" rebar. Installed monument over existing 1/2 inch rebar, with top 1 foot below ground level. Established additional new references, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

83: Set 2 1/4" x 30" Aluminum Monument
w/3 1/4" Aluminum cap stamped to I.D.
corner position. Est. reference trees
w/BT signs, blazed, scribed and painted.
Set PK nails for measuring w/brass I.D.
washers in the following reference
trees. Maple 16", S.23 E., 67.30 feet,
"1/4S-BT". Exist - Maple 16", S.29 W.,
37.81 feet, "BT". Exist - Beech 20",
N.50 E., 82.64 feet, "BT". Exist -
Hemlock, 24", North, 53.98 feet, "BT"

Signed by Robert L. Jamros Date 1 June, 1994

Surveyor's Michigan License No. 25849