SURVEY & REMONUMENTATION

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8 19

Gerald W Carlson

MAY 1 0 1995

LAND CORNER RECORDATION CERTIFICATE

4-284

Citations	Filing Requir	rement of Act 74, Mich. P.	1.1970° 7° 207
For corners in			
Alger (County)	Located In:	Corner Code ##	FILED
County		ļ	
Public Land Survey	T <u>46N</u> R <u>18W</u>		ME 9:00 a.m.
•	T R		
	T R		APR 20 1995
	T R		
2. Property Controlling	S T R		DONALD W. LINGUIGY
in Section	\$ T R		REGIO TRICILITATION
3. Miscellaneous	S T R		Register of Deeds Stamp & File Number
Property in Sec.	S T R		
I. Robert L. Jauros do hereby certify that under rein lines 1 and 2 above were current manual of survey inst Management or by a decree of above were in conformance with Court of Law; established, expressed below:	Recorded Plat	enber 18, 1994, 19 Lof 1970, the corner points mention of rules therefore as required in the interior, Bureau of Ler points mentioned in lines 3, 4 are of Land Surveyors or by a Decree monumented. recovered, found	2 6 5 3 2 3 4 7 8 9 10 11 12 ned the and 7 nd 5 8 19 20 21 22 23 24 of a
on this certificate	corners, all in the same town a e.	ind range, may be recorded	12 31 32 33 34 35 36
A. Description of original	I monument and accessories an	id/or subsequent restoration:	···
			arack 8", N.47 E., 47 links, Tamarack 12", N.48
			Corner shown South of Co. Hwy. H-58, (Old State

3-339, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Cl: Found 2" cast steel nonument with 3 1/4" brass cap marked to identify corner position. A search was made for evidence of GLO BT's, evidence inconclusive. In report of R.L.Jamros, 1988, corner position was located by field survey as part of a section subdivision survey. Corner was located from centerline measuring 975 ft. south of County Hwy. H-58 (Old State M-94). There is no record of this monument being set but it is typical of the monuments being used by the County Surveyor for Alger County the early part of this century. The cap was marked well but without a date. Established additional reference trees. Accepted the existing monument as the best available evidence of the position of the original corner.

M-94), 975.89 feet to a 2" Iron Pipe w/ cap. M.Pine 24", S.29 E., 10.19', Balsan 7", S.50 N., 16.40', Maple 6", N.31 N., 23.32', CCI Land Cor. Record No. 1074, J.R. Radcliffe, RLS, 1967, Iron w/ brass cap. New Ref. Maple 5", N.31 N., 34.8 links, W.Pine 22", S.26 E., 14.4 links. Robert L. Janros, RLS, 1988, Found Iron w/ brass cap and Two BT's. References: Maple 10", N.31 N., 23.2 ft., Existing., Pine Stump 30", S.23 E., 10.0 ft., Existing., Balsam 5", N.57 E., 23.2 ft., Hemlock 5", S.17 N., 12.3 ft. Recorded in Corner Record No.

Cl: Stamped P.A. 345 in brass cap of 2" cast steel monument. Renewed existing and established new reference trees w/ BT signs and paint. Set Pk nails for measure w/ brass I.D. washers in the following reference trees. Ex. Maple 10", N.27 W., 23.14 feet, "Dbl. Blz'd", Ex. Spruce 7", N.60 E., 23.20 feet, "S32 BT", Ex. Henlock 6", S.21 W., 12.30 feet, "S6 BT", Maple 6", S.62 E., 6.56 feet, "S5 BT", Steel witness post with Survey marker sign, N.50 E., 2.0 feet, All bearings are magnetic.

		/i /		·	
	LA +	7 & James	Date	12 April 1995	
Signed by	pru) W. James	Date	12 April, 1775	
Surveyor's Michigan L	icense No	25849		FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAI REVISED MA	