

SURVEY & REMONUMENTATION

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8-1995

MAY 10 1995

COMMISSION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-285

Harold W. Carlson
Chairman

For corners in

Alger <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>46N</u> R <u>18W</u>	<u>C2</u>	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

FILED
MAY 9:00 a.m.

APR 20 1995

DONALD W. LINNUNEN
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	●	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on November 11, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C2: PLS-George E. Adair, DS, 1855, Set Qr. Section Post- Spruce 7", N.27 W., 20 links, Tamarack 12", S.56 1/2 E., 30 links. CCI Forestry Division, Land and Timber Examination Report. R.J. Brotherton, RLS, and J.R. Radcliffe, RLS, indicate corner as post, 4" Sq. Spruce and down Tamarack GLO BT, 1943 through present.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C2: Began at corner of Sections 5 and 6, T.46N., R.18W. and Sections 31 and 32, T.47N., R.18W., Ran corrected compass line on GLO bearing south. At 7.2 ch. (GLO 7.17 ch.) found remains of W.Pine stump, 42" estim. (GLO 28"). At 31.92 ch. (GLO 31.87 ch.) found W.Pine stump, 32" estim. (GLO 14") on top of knob, GLO combined call. Found axe pointed post point at 40.45 ch., GLO 40.37 ch., remains of post have decayed beyond recovery. From post point location of 40.45 ch. located stump remains of Tamarack in the GLO BT location of S.56 1/2 E., 30 links. Tamarack log is down and badly decayed. Replaced post point with monument and established reference trees. Corner lies in thick, wet Spruce marsh. Found old blaze line running north from corner position. Corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C2: Set 2 1/4" Alum. Monument w/ 3 1/4" Alum. Cap stamped to identify corner position. Established reference trees w/ BT Signs, blazed, scribed and painted. Set PK nails for measure w/ brass I.D. washers in the following reference trees. W.Pine 20", N.69 W., 22.90 feet, "1/4s BT", W.Pine 10", N.22 E., 20.88 feet, "1/4s BT", Maple 10", S.33 E., 33.74 feet, "1/4s BT", W.Pine 22", S.42 W., 65.07 feet, "1/4s BT", Steel witness post with Survey marker sign, N.42 W., 2.0 feet, All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12 April, 1995